


The APS Upgrade



John Carwardine

APS Upgrade

Deputy Associate Project Manager - Accelerator

Argonne National Laboratory

June 13, 2018

The Advanced Photon Source: BES's largest user facility


ARGONNE NATIONAL LABORATORY 400-AREA FACILITIES

ADVANCED PHOTON SOURCE

(Beamlines, Disciplines, and Source Configuration)

ADVANCED PROTEIN CHARACTERIZATION FACILITY


CENTER FOR NANOSCALE MATERIALS



- APS is an xray microscope
 - In operation since 1995
 - 7 GeV electron synchrotron
 - 1104m circumference
 - Hard xrays: 1KeV – 100KeV
- 68 simultaneously operating end stations
- 5000 operating hours/year, 98% availability
- FY17: 5700 unique users, 700 institutions
- FY17 operating budget: \$134M

To stand still is to lose ground



The push now is for higher brightness and transverse coherence, smaller spot sizes



Brightness and coherence scale inversely with emittance

Reducing emittance from **3100** pm-rad (APS) to **42** pm-rad (APS-U)

- ⇒ 2 orders of magnitude higher brightness and transverse coherence
- ⇒ smaller spot size for microprobes
- ⇒ round beams
- ⇒ **New science capabilities**



Emittance scaling

$$\varepsilon_x = C_L \frac{E^2}{N_D^3}$$


E = Beam energy ($E = 6$ GeV for APS MBA)

N_d = Number of dipoles per sector ($N_d = 7$ for APS MBA)

APS - 7 GeV, 2-bend lattice



~70-fold reduction in horizontal emittance



APS-U replaces this with this

APS-U - 6 GeV, 7-bend lattice

APS-U Project Scope

All existing beamlines incorporated in plans to come back online at conclusion of APS-U

Feature beamlines
Suite of beamlines designed for best-in-class performance

Beamline Enhancements:
improvements to make beamlines "Upgrade Ready"

"Do no harm"

New Storage Ring

- 6 GeV MBA lattice
- **42 pm-rad emittance @ 200 mA current**
- Improved electron/photon stability

New Insertion Devices

- Incorporate **SCUs** on selected beamlines


New/upgraded Front-ends

- Common design for maximum flexibility
- Integrated hard x-ray beam position monitors

Injector improvements


- Increased performance (high single-bunch charge)

Utilizes \$1.5B in existing infrastructure




APS-U 42-pm Lattice



- Storage ring consists of 40 Sectors. Each with 33 arc magnets; 27.6 meters / sector
- Each sector is a hybrid 7BA with four longitudinal-gradient dipole bends, three transverse-gradient dipoles, and six reverse bends.
- Vacuum systems integrated with magnets, supports, insertion devices, front ends.




APS Upgrade Project Schedule




APS-U Technology



L-Bend Magnets (M1, M2)





In-House Design
Fast Bipolar Power Supply*




Higher-order
mode damper
(four units exist)

Single Cell 1.4 GHz
Superconducting
Harmonic Cavity (two
in house)


Fundamental Power
Couplers



Q-Bend Magnets M3,M4






Exploded view of planar SCU design model with
vacuum chamber



Prototype Stripline Kicker used for successful BTX Beam Tests

Fast Bunch Swap-Out Injection

Prototype Stripline Kicker* used for successful BTX Beam Tests



Operation demonstrated with beam to 30 kV; double the original requirement.

MBA Control System constraints and challenges

- Control system design **retains the underlying APS controls infrastructure**
- Enhancements are driven by APS-U technical system needs
 - Ubiquitous embedded IOCs, FPGA-based controllers, network appliances
 - Substantial increase in number network ports
 - Substantial increase in data volume and throughput requirements
- Commissioning time is short for Controls + Integrated Tests + full MBA
 - Must be completely integrated/tested/debugged very soon after installation
 - All tools must be debugged and ready
 - Requires expedient troubleshooting tools
 - **Early deployment of “virtual accelerator systems” with production PV names**
 - **Early development of integrated tests (using the virtual accelerator and test stands)**
- Will need to draw upon the numerous ‘modern’ tools developed by the EPICS community

Major challenge – 12-month dark-time schedule

TASK	Removal		Installation						Commissioning			Float
	Month 1	Month 2	Month 3	Month 4	Month 5	Month 6	Month 7	Month 8	Month 9	Month 10	Month 11	Month 12
Remove IDs and front ends	█											
Remove mezzanine electronics	█											
Remove magnet girder assemblies	█											
Prepare tunnel surfaces		█										
Install magnet modules			█	█	█	█	█	█				
Install mezzanine electronics			█	█	█	█	█	█				
Install front ends			█	█	█	█	█	█				
Install insertion devices				█	█	█	█	█				
Integrated system testing w/o beam				█	█	█	█	█				
Accelerator Readiness Review						█	█	█				
Commissioning									█	█	█	
Float												█

- 3-month beam commissioning phase begins in Month #9
- Control System will be expected to be ready from the moment it's needed
- Transferring Controls interfaces from existing technical systems to new will be a daunting task (~500,000 PVs, over 21 new systems)

From PDR **MBA Control System Scope**

Control System Engineering

Applications & Services

Technical System Database
(magnet measurements, calibration data, installed equipment, etc)

Subsystem Performance Monitoring

Subsystem Integration Tests

APIs to other toolkits (e.g. Matlab, Octave, python)

Short Term Data Logging

BPM / Orbit Server

Process Variable Database

Power Supply Synchronous Setpoint Control

Data Acquisition (DAQ) Services

Physics Applications & Operation Tools

Interactive Tools

Convenience Tools for Operators

Injection Sequencer

Alarms

sdds tools


Long Term Data Logging

Post-mortem analysis

AOP Applications

- 1000's of scripts
- MPS Data Review
- Knobs (weights/limits)
- Glitch Logger
- PEM
- sddsexperiment
- BPM Histories


EPICS





Controls Hardware & Software Infrastructure



Interface(s) to Technical Equipment




Timing & Synchronization





- Real-time processing workflow**
- 1 : DAQ Setup
 - 2 : Start Data Acquisition
 - 3 : Stream DAQ Data to Data Collector
 - 4 : Save Files to Local Storage
 - 5 : Initiate Real-Time Processing Workflow
 - 6a: Process Data
 - 6b: Save Processed Files
 - 6c: Notify SDDS To PV Object Service
 - 7 : Convert SDDS Files to PV Objects
 - 8 : Update PVA Channels
 - 9 : Receive PVA Updates

OrbitVectorServices
 [method = AClockin]
 [event = beam-loss]

DAQ Use Case: Monitoring SR Injection




APS-U fast orbit feedback



- The APS orbit feedback system was the first digital truly global fast orbit feedback system to be implemented at a light source
 - In operation since 1995

- APS-U fast orbit feedback follows the same architecture and design philosophy (it just uses 'modern' technology)

APS-U Orbit feedback Integrated R&D



Fast orbit feedback system parameters

Present system (circ. 1995)

Parameter	APS-U design	'Datapool'	RTFB
Algorithm implementation	'Unified feedback' algorithm ✓	Separate DC and AC systems for slow and fast correctors	
BPM sampling & processing rate	271 kHz (TBT) ✓	10 Hz	1.5 kHz
Orbit correction update rate #	22.6 kHz ✓	10 Hz	1.5 kHz
Signal processors (20 nodes) (one node demonstrated)	DSP (320 GFLOPS) + FPGA (Virtex-7)*	EPICS IOC	DSP (40 MFLOPS)
Num. rf bpms / plane	570 *	360	160
Fast correctors / plane	160 *	-	38
Slow correctors / plane	320 *	282	-
Fast corrector ps bandwidth	10 kHz ✓	-	1 kHz
Fast corrector latency	<10 us ✓	-	~250 us
Closed-loop attenuation bandwidth	DC to 1 kHz**	DC - 1 Hz	1 Hz - 80 Hz

Highest demonstrated at any light-source to date

✓ Demonstrated

* Full double-sector demonstrated

** >800 Hz has been demonstrated

Wrap-up

- The APS-U lattice design has the lowest horizontal emittance of all synchrotron light sources currently under consideration (42 pm-rad)
- APS will continue operating until mid FY2022
- APS-U is due to come on line in FY2023 after a 12-month shutdown
- APS-U R&D program has been very successful (for Controls and others)
- Early procurements are underway (magnets, power supplies,...)
- There are many challenges (for Controls and others)
- We have funding (FY2018 budget = \$93M)